

Proposed Winter Maintenance Works – to be carried out between December 2016 and March 2017

Dryburgh Gardens-

Improvements work to relocate S1 shrub bed

S1 – remove old Rose & roots from existing location

- Cultivate soil and prepare for turf

New S1 – new location as directed

- lift existing turf on site to form new bed (35m²)
- turf relay on old bare bed and dress in
- cultivate and compost new bed
- define grass edge

Supply and Plant – as directed

1 Colorado Blue Spruce (specimen conifer – stake / tie)

6 Black-eyed Susan

6 Sage

12 Japanese Spurge

12 Thrift

12 Cupid's dart

6 Elephants ears

12 Heather - Springwood White

6 Ruthenian globe thistle

3 Hosta fortunei picta

12 Heuchera Scintillation

12 Primula denticulate

6 Festuca glauca

NO WEEDKILLER to be used in maintaining this new bed

Fintry – various areas

Finella Terrace

G27 – additional work at no,63

Mature Acer tree – reduce head (1/3rd)

Acer tree at lamp post – reshape head

G28 – 3 Acers (900 / 1,400mm x 2) Remove / stump and reinstate

G27 – 2 Acers (1,400mm x 2) Remove / stump and reinstate

Fintryside

G294 – at no.95

Lime tree – reduce head and crown raise at dying area

S109 – Rowan tree – crown raise at drying area

S111 – remove old shrubs / grind out roots and old tree stumps / Cultivate bed / soil up levels

Grass seed in 25m² – **March 2017**

S106 - remove old shrubs / grind out roots and old tree stumps / Cultivate bed / soil up levels

Grass seed in 60m² – **March 2017**

Finmore Street

G25 – 2 Acers (1,300+1,400mm) remove / grind stump and roots and reinstate

Finella Gardens

G100 – Mature Poplar (1,400mm) remove / stump and reinstate
Acer at no.37 – reduce and reshape in head

Finavon Street

G59 – Cherry (1,500mm) remove / stump and reinstate
F2 – trees marked for removal 4 Ash (600-800mm) : 2 Acer (1200mm x 2)
Tree branches at nos 30/32 – chip up into bed

Fintry Mains

G1a – boundary fence line Cut back branches and limbs overhanging at building and seated area

Americanmuir

Boundary line between 79/81 Camperdown Rd

Beech trees / scrub at boundary will no.79 – hard prune and shape into 1.8m hedge (**access from no.79 garden**)

G4 – Mature tree – reduce & thin head (1/3rd in volume)

Kirkton

G11 – 2 Mature Cherry trees (1,400 + 2,000mm)

Remove / grind stumps and roots and reinstate

Cherry tree in garden (51 Helmsdale Avenue) – cut back limbs overhanging fence and prune clear of telegraph pole.

G14 – 2 Ash trees – crown raise and tidy up lower limbs

Acer – crown raise

Pitalpin

G2 – Alnus tree crown raise

G4 - 2 Ash trees prune in heads

Acer – reduce head

G17 – 2 Acer trees reduce and thin head

G50 – Acer tree at path Crown raise

G49 – Prunus tree (1,200mm) at lamp post Remove / stump and reinstate

Acer tree at roadside – crown raise

G37 – Acer tree (1,200mm) Remove / stump and reinstate

Acer tree at 27 Broomlee Road – prune branches towards house and reshape

G38 – Acer tree at 17 Laggan Gardens - prune branches towards house and reshape

Broomlee Road / Laggan Gardens – G37 to G39 stop car trespass

Construct timber trip rail – 100mm fixed posts / angle cut and 600mm high rail 75mm on the angle / secured and metal straps fixed

1 section at 3m / 1 section at 6m & 1 section at 2m

William Street

S22 – remove ALL shrubs on Abertay section / grind roots and stumps / cultivate / soil up levels and grass seed (40m²) into **G18**

(March 2017)

Step Row

S3 – remove old Rose shrubs / cultivate / soil and turf in 20m²

S4 – bare section Cut away Ivy off wall / remove sapling and debris

Cultivate / compost and plant – 10 Photinia red robin and 10 Cherry Laurel otto luyken

S9 – replacements – 4 Sedum Spectabile Autumn Joy

4 Sage and 4 Heather springwood white

Caldrum Street

S9 – Birch tree crown raise

S10 – No.30 remove Pyracantha shrubs / grade over / terram and gravel in (20mm washed) strip 4m x 600mm

S22 - remove Pyracantha shrubs / grade over / terram and gravel in (20mm washed) strip 3m x 300mm

S21 (hedge) - remove Eleagnus shrubs / grade over / terram and gravel in (20mm washed) strip 11m x 600mm

Gravel drying area at no.55 – rake over / remove moss / grade levels / supply and spread 1 tonne 20mm washed to dress over

Rosebank Street

S1 – Rowan tree reshape and thin head

Gordon Street

Remove Acer limbs towards house and overhanging roof of 55 Coupar Street

S2 – replacements 12 Honeysuckle baggesons Gold

S14 – remove old Rose and sapling / cultivate / soil and compost in 4m² Supply & plant:- 1 Photinia red robin / 9 Hebe midsummer beauty

Lawrence Street

S4 – 2 Acer trees and 1 Birch tree Crown raise

Malus at seat – trim in head

S15 – remove shrubs and roots / grade over / terram and gravel in 8m²

No.12 Fyffe St – rear drying area

Uplift uneven slab in drying area

Sever tree roots and remove

Rebed base and relay slabs

Dura Street

Improvements and reinstatements work following building works

Reinstatement work – after building work

S5 & G6 – rear 68 to 72 Brougham Gardens

Stump grind old Acer regenerated tree stump

Remove old Rose & Cotoneaster shrubs at houses and side wall

Retain Skimmia shrubs at side fence

Remove roots and stumps / cultivate / soil up levels and turf in 50m² into G6

At building form a strip 300mm wide below turf edge and gravel in with 20mm washed (30m x 50mm)

S42 – rear no. 56 Dykehead Place

Remove old Rose and roots

Cultivate bed / soil up levels and turf into G17a – 10m²

S19 at pathway (side of Common room)

Cut away existing shrubs / remove stumps / Cultivate / soil and compost up levels: - 20m²

Supply & Plant – as directed

12 Heuchera Scintillation

6 Elephants Ears

6 Choisya ternata

3 Japanese Laurel (3 – 5 lit pots)

6 Weigela hortensis

12 Hebe Midsummer Beauty

S22 – opposite entrance Common room

Cut away existing shrubs / remove roots / old tree stumps to grind out / Cultivate / soil and compost up levels: - 40m²

Supply and Plant – as directed

12 Cupid's Dart

6 Elephants Ears

12 Heather Springwood White (1lit)

6 Globe Thistle

3 Hosta fortunei picta

12 Heuchera Scintillation

12 Japanese Spurge

3 Rhododendron Elizabeth (3lit)

20 English Lavendar

6no Black-eyed Susan

S5a at gable end 72 Bougham Gardens

Remove shrubs and stumps / reduce soil levels / grade / terram and gravel in (20mm washed – 9m² x 50mm)

S34a at gable end 51 Dykehead Place

Remove shrubs and stumps / reduce soil levels / grade / terram and gravel in (20mm washed – 3m² x 50mm)

Improvements work – OSM works**S51a (sloped bed) – rear 64 to 78 Dykehead Place**

Sever Ivy and remove off brick building wall

Elder saplings at metal boundary fence and timber fence section – cut back

Reduce to ground level ALL tree saplings / suckers in bed

Reduce large shrub sections to 600mm (Pyracantha)

Sections of Blackberry and Cotoneaster ground cover prune back to 300mm of ground

Remove all spoil and debris exposed

Site boundary wall on Ogilvie Street

Cut out Buddellia saplings (14 – 18 Brougham Gardens)