

Abertay Open Space Maintenance Winter Works 2018/19

Winter Tree works

Pitairlie Road Complex

Crown raise Prunus tree and reduce Elder by 50% in rear garden area.

Hard prune Privet and Hazel hedging and prune back tree and pine branches which are encroaching building.

Kirkton Estate

G8 - Remove 2 Mature Acer trees, stump grind and soil in pits.

G14 – Prune back branches of 2 Pine trees, which are overhanging road.

Pitalpin Estate

G10 – Remove Alnus tree, Ash tree and trim back branches of Sorbus tree.

G32 – Remove Prunus tree, stump grind and reinstate pit.

G32 – Reduce and thin head of Sorbus tree.

G30 – Crown raise Alnus tree.

G50 – Crown raise Lime tree next to road side.

Donald's Lane

G1 – Remove dead limbs from Acer tree.

Step Row

G3 – Remove top and reshape Mature Conifer.

Americanmuir Road Estate

G5 – Remove Acer tree, stump grind and reinstate.

G5 – Crown raise trees at boundary fence and garage lock-up area.

William Street

S4 – Remove Sorbus tree.

S25 – Clear away scrub and ivy from site boundary wall.

Fintry Estate

Fintry Mains

G13 – Prune scrub and ivy at boundary fence to form hedge line.

Finavon Street and Findhorn Street

Thin out line of trees to maintain single line of trees where possible, along tree belts which form screening for Forfar Road dual carriageway.

Finlow Terrace

G276 - Remove Prunus tree at lamp-post, stump grind and turf in pit outside no 3.

G275 - Remove Prunus tree at car parking bay, stump grind and turf in pit outside no 5.

G273 - Remove Prunus tree at path, stump grind and turf in pit outside no 7.

G268 - Remove Prunus tree at gable end, stump grind and turf in pit outside no 11.

G260 - Remove Acer tree at gable, stump grind and turf in pit outside no 17.

G254 - Prune head to reshape Prunus tree outside no 21.

G248 - Remove Acer tree, stump grind and turf in pit outside no 27.

Finella Gardens

G99 – Remove Lime tree, stump grind and turf in pit.

G99 – Stump grind mature stump and reinstate with turf.

G100 – Prune branches of Acer tree towards no 35 and prune branches of Acer tree next to path.

Cheviot Crescent

G379 – Reduce head of Prunus tree at Liff Resettlement Project.

Fintryside

G284 – Remove Ash tree, stump grind and turf in pit.

G309a – Remove 2 Prunus trees, stump grind and turf in pits outside no 100.

G299 - Clear low overhanging branches from 1 Sorbus tree and reshape and remove Acer tree, stump grind and turf in pit.

Findale Street

Reshape scrub and sucker growth at embankment area along top fence line to form an informal hedge line.

Clear main trunk of Acer tree, Remove 2 Lime trees and prune back limbs from 1 Lime tree which are overhanging drying areas along back of 1-9 Findale Street.

Prune back limbs of 3 Lime trees which are overhanging the drying areas at the rear of 11-17 Findale Street.

Crown raise 2 Lime trees and reduce head of another 1 Lime tree in the open embankment areas.

Winter works to soft landscaped areas

Pitairlie Road Complex

Cut scrub and stumps before preparing and turfing in 27m² at rear garden area.

Gordon Street

Revamp area S15 by uplifting and setting aside some perennials, removing old Berberis shrubs and grading and replanting additional plants.

Craigiebank

S1 – Compost and re-plant area.

Kirkton Estate

G8 – Supply and plant 1 Sorbus aria tree pit in composted pit.

G8 - Repair damaged area and reinstate grass 80m².

Caldrum Street Estate

Revamp area S6.

G2 – repair damaged grass, prepare, re-soil and turf in 2m².

S5 – Remove old shrubs and roots and remove severe ivy from Birch tree.

Prepare, soil and turf in 25m² to G1.

Pitalpin Estate

Revamp area G47.

Dura Street Estate

S3 – Remove damaged shrubs and roots and prepare, soil and turf in 30m².

S30 - Remove damaged shrubs and roots and prepare, soil and turf in 16m² into G12.

S28 - Remove damaged shrubs and roots and prepare, soil and turf in 15m².

S29 - Remove damaged shrubs and roots and prepare, soil and turf in 10m² into G27.

S34 - Remove damaged shrubs and roots and prepare, soil and turf in 4m² into G18.

G18a – Grass repairs and reposition grit bin on slabs.

S51c – Remove mature shrubs and roots and prepare, soil and turf in 25m² into G23a at rear of 18-28 Dykehead Place)

S44 – Remove mature shrubs, tree and roots and prepare and soil, compost and replant bed 12m².

S43 - Remove mature shrubs, tree and roots and prepare and soil, compost and replant bed 24m².

S45 - Remove mature shrubs, tree and roots and prepare and turf in 45m² into G24 and 600mm gravel strip along front of building.

S46 - Remove mature shrubs, tree and roots and prepare and turf in 50m² into G19 and 600mm gravel strip along front of building.

S47 - Remove mature shrubs, tree and roots and prepare and turf in 20m² into G19 and 600mm gravel strip along front of building.

S48 - Remove mature shrubs, tree and roots and prepare and soil, compost and replant bed.

Winter works to hard landscaped areas

Dura Street

S2 – Remove damaged shrubs and roots before preparing ground using Teram, type 1 material and gravel in 28m² at front of 17-21 Brougham Gardens.

S10 – Insert 3m of edging kerb and gravel in 5m² at front of 36-54 Brougham Gardens.

S8 – Remove all damaged shrubs and roots and gravel in 15m². Also prepare base for slabs and timber trip rail for repositioning Euro Bins.

Repair damaged slabs at front of block 36-54 Brougham Gardens.

S33 – Remove old Rosa before soiling and slabbing in 7m² on corner at rear of 43 Dykehead Place.

G12 – Remove bare soil and define edge between grass and new gravel area.

S26 - Remove old Rosa before gravelling in 6m² at rear of 33 and 35 Dykehead Place.

S32 – Remove damaged shrubs and roots before preparing ground using Teram, type 1 material and gravel in 24m² at front of 3-7 Dykehead Place.

G17 – Uplift grass at recycle bins and prepare base with slabs for bin store area.

G24 – Define grass edging using kerb and gravel in front of 30-40 Dykehead Place.

Kirkton Estate

G6 – Prepare base for concrete slabs and reposition grit bin.

G8 – Extend car parking bays by 6m x 5m by uplifting grass and soil and reinstating with teram, type 1 material and spreading with top coat of whin dust, rolled.

Pitalpin Estate

Uplift slabbed path and tree roots before preparing and resetting slabs on common footpath outside 14 Portmore Place.

Dunholm Mews Estate

Prepare base for laying concrete slabs to reposition grit bin.

Dunholm Gardens Estate

Prepare base for laying concrete slabs to reposition grit bin.

Step Row

S2 – Remove Ivy at wall, remove shrubs and roots and reinstate with gravel strip and turf 30m².

Lawrence Street Estate

S16 – Remove shrubs and roots and prepare and soil and seed 140m² (springtime).

Peddie Street Estate

Boundary wall – cut down scrub and ivy on wall.

Rosebank Street Estate

Boundary wall – hard prune Ivy at wall and remove to expose coping slabs.